

Project Scope – Ramsay Street, Thangool – Pathway

Project Name: Ramsay Street Pathway Replacement

Description of Project: Replacement of the existing cracked concrete pathway between the buildings on the southern side of Ramsay Street (Burnett Highway) between Winston Street and Llyod Street Thangool.

Construction Notes: Work is not to commence before 7am each day so as to minimise the disturbance to neighbouring residents. Access to the neighbouring properties is to be maintained where possible, should an access need to be cut off at any time Council is to be notified a minimum 48 hours before the restriction is required so contact can be made with the resident to arrange for alternative access. The project site is to be secured outside of work hours in such a way as to minimise the risk to the safety of pedestrians and residents in the area.

Project Scope:

Location	Description of Works	Length (m)	Width (m)	Depth (mm)
Section 1	<ul style="list-style-type: none">• Removal and stockpiling for later use of topsoil alongside the pathway• Removal and disposal of the existing pathway• Installation of concrete reinforced pathway (reinforcement to be minimum SL62) along previous alignment• Backfilling and relaying of the topsoil beside the pathway	30	1.2	100
Section 2	<ul style="list-style-type: none">• Removal and stockpiling for later use of topsoil alongside the pathway• Removal and disposal of the existing pathway• Installation of concrete reinforced pathway (reinforcement to be	9	1.2	100

	minimum SL62) along previous alignment <ul style="list-style-type: none"> • Backfilling and relaying of the topsoil beside the pathway 			
Section 3	<ul style="list-style-type: none"> • Removal and stockpiling for later use of topsoil alongside the pathway • Removal and disposal of the existing pathway • Installation of concrete reinforced pathway (reinforcement to be minimum SL62) along previous alignment • Backfilling and relaying of the topsoil beside the pathway 	24	1.2	100
Section 4	<ul style="list-style-type: none"> • Removal and stockpiling for later use of topsoil alongside the pathway • Removal and disposal of the existing pathway • Installation of concrete reinforced pathway (reinforcement to be minimum SL62) along previous alignment • Backfilling and relaying of the topsoil beside the pathway 	27	1.2	100

Locations:

