

Project Scope – Tognolini Baldwin Road, Biloela – Pathway

Project Name: Tognolini Baldwin Road Pathway Replacement

Description of Project: Replacement of the existing cracked asphalt pathway on the southern side of the road between Jambin Dakenba Road and State Farm Road. New pathway is to join to the existing concrete pathway just before the State Farm Road intersection.

Construction Notes: Pathway can be closed between the two intersections for the duration of construction if necessary. No work is to occur before 7am when working within 150m of an occupied residence.

Project Scope:

Location	Description of Works	Length (m)	Width (m)	Depth (mm)
Section 1	<ul style="list-style-type: none">• Removal and stockpiling for later use of topsoil alongside the pathway• Removal and disposal of the existing pathway• Removal and disposal of the concrete sections of pathway• Installation of concrete reinforced pathway (reinforcement to be minimum SL62) along previous alignment – adjustment is to be made to the alignment if necessary to ensure that there is no requirement for the removal of existing trees.• Tapering and merging of the pathway to match the pedestrian bridges (x2) along the pathway alignment• Relocation of seat (if required) to allow for the required pathway width	873	2	100

	<ul style="list-style-type: none"> • Backfilling and relaying of the topsoil beside the pathway 			
Section 2	<ul style="list-style-type: none"> • Increase of thickness of pathway at entrances from 100mm to 150mm (5 in total) 	38	2	Extra 50mm

Locations:

