

T2324.18 DRFA PROGRAM DRAINAGE RECONSTRUCTION WORKS 2023-2024

Notice to Tenderers

NOTICE TO TENDERERS NO: 2

Banana Shire Council (BSC) has received a query with respect to the Tender. The following has been reviewed:

ADDIOTNAL DOCUMENT

Banana Shire Council has identified and added the following documents and information:

- MRTS70
- TN187

And flowable fill is to be in accordance with MRTS03, MRTS04, MRTS70 and the attached Technical Note.

18.4 Controlled low strength material (flowable fill)

Controlled Low Strength Material (CLSM) shall be supplied to meet a specified strength range. Slump shall be nominated as between 180 and 200 mm.

Care shall be taken during placement to avoid floatation or dislodgement of conduits, pipes and formwork.

Technical Note 187 Controlled Low-Strength Material for Pipe Installation describes CLSM for pipe installation.

MRTS04 General Earthworks nominates what strength is required for different backfill operations.

Tender Submission

Tender Response and attachments will be accepted via email submission to tenders@banana.qld.gov.au or via Dropbox. Hard Copies are not required.

Dated: 18th December 2023