



# SCOPE OF WORKS

KELLYS ROAD DON RIVER BANK STABILISATION

Contract No: T2425.30

*(Revision 4)*

## **1. THE SCOPE OF WORKS**

- 1.1 **(Documents comprising this Scope of Works)** The Scope of Works comprises this Scope of Works, including;
- (a) Appendix A – General Specification
  - (b) Appendix B - Site
  - (c) Appendix C – Price Schedule
  - (d) Appendix D – Design
  - (e) Appendix E – Technical Specification
  - (f) Appendix F – Minimum Traffic Signage Requirements
- 1.2 **(Precedence of documents comprising the Scope of Works)** The documents comprising the Scope of Works shall be taken to be mutually explanatory. If there is any ambiguity, inconsistency, conflict or discrepancy between any of the documents listed in clause 1.1 then the documents will take precedence in the order set out in clause 1.1, with the document listed at 1.1 being the highest in the order.
- 1.1 **(Documents incorporated by reference into the Scope of Works)** The Contractor is deemed to have obtained copies of, read, understood, and allowed for compliance with the Scope of Works (including any documents which are incorporated into it by reference only).
- 1.2 **(Definitions)** Capitalised terms used in the Scope of Works have the meanings assigned to them in the General Conditions of Contract (if any) unless the context otherwise requires. Terms which are separately defined in a clause of this Scope of Works have the meanings given in those clauses.

## **2. SCOPE OF WORKS**

- 2.1 WUC comprises, but is not limited to the following road remediation works treatments
- (a) Geotextile Installation;
  - (b) Clear, grub and dispose of material off site
  - (c) Detailed excavation to meet required profile and remove spoil from Site
  - (d) Road Edge Guide Posts
  - (e) Grade and trim pavement box. Road formation in accordance with QRA Treatment Guide.
  - (f) Supply, load, cart, spread and compact TMR Type 2.3 base course material (compacted volume)
  - (g) Speed Limit Sign installation
  - (h) Supply and Install Soil Nails

## Project Brief

- (i) Supply and install Horizontal Drains in accordance with Project Drawings
- (j) Supply and Install, Mac-Mat-R accordance with Project Drawings.
- (k) Supply all plant, labour and materials required to install geofabric backing to rock armouring (Section A + Section B).
- (l) Supply all plant, labour and materials required to load, cart, spread and compact Rock Armouring & Rock Toe (Section A and B)

as more particularly described in the Appendices to this Scope of Works.

2.2 WUC is to be carried out at the locations identified in Appendix B – Site.

2.3 Except to the extent expressly permitted by the Contract, the Contractor must carry out WUC in accordance with the with Appendix D Design, Appendix E– Technical Specification, Appendix A - General Specification.

## Appendix A – General Specification

---

## Appendix B – Site

For the purpose of the definition of "site" in the General Conditions of Contract, the Principal will make available the lands and places identified in this Appendix B.



